

TRUCKBAY / SLW 60
VP 700010

The intelligent prefabricated steel pit for maximum efficiency and safety!

The TRUCKBAY is the ideal solution for efficient and safe repair, maintenance and inspection work on all commercial vehicles and buses - up to a total weight of 60 tonnes. The customised, self-supporting, prefabricated steel pit allows quick installation without time-consuming construction work. Thanks to different standing heights, anti-slip flooring (R12) and oil and watertight welding, it offers maximum ergonomics and safety. Its own structural design creates a stable, seamless connection to the workshop hall.

With flexible equipment solutions, integrable testing technology and optional sliding cover, the TRUCKBAY takes efficiency to a new level.

PRODUCT DETAILS/ACCESSORIES

Standing height 1.50 or 1.60 m in connection
with pit length selectable at options.

Description:
Maintenance pit / Test pit
Double wall design

The double wall prefabricated pit includes
- Top pit frame to accommodate covers
- Beam in the head area to accommodate a pit jack with support system up to 15.0 t / a waste oil collector / or similar
- Bottom grating in hot-dip galvanised grating design, slip-resistant R12
- Optionally selectable are pit lanes, electric supply with sockets, pit lighting, compressed air supply, oil disposal, installation frames for roller test benches and axle play testers, rails for floor-running pit jacks
- Pit bottom with slope to pump sump/drain
- Piping forventilating prefabricated pit with central air outlet
- Coating inside prefabricated pit: 2-component active primer / 2-comp. top coat in RAL 7040
- End and side walls in double wall design for the on-site concrete filling acc. to construction stage description
- Supporting feet incl. safety heavy-duty anchors for fastening the prefabricated pit on base plate

The prefabricated pit meets the requirements of
water protection acc. to WHG/VAwS (AwSV)/TRwS (779/785/786)
and the requirements of occupational health and safety
acc. to ArbSchG/BetrSichV (Germany)

Special TRUCKBAY payment terms:
50% down payment upon order placement
40% when ready for delivery
10% after installation

Production does not start until the installation drawing has
been approved and after receipt of the down payment.
All positions are net prices.

TECHNICAL DATA

Pit opening	1.02 m
Lower pit width	1.62 m
Support profile	Roll cover
Pit jack and support system	U 260
Load	designed as per SLW60, DIN EN 1991-1-1:2010-12
	DIN EN 1991-1-1/NA:2010-12
	DIN technical report 101:2009-03
	and DIN 4085 supplementary sheet 1:2011-12
Surface load	60 t

TECHNICAL DATA

Axle load	20 t

ACCESSORIES

VZ 920030	TRUCKBAY Standing height 1.50 m Pit length per meter
VZ 920031	TRUCKBAY Standing height 1.60 m Pit length per meter
VM 999083	TRUCKBAY Mounting material MTZ Pit length per meter
VZ 920032	TRUCKBAY Enlarged pit opening Base frame 1.10 / 1.22 m
VZ 920033	TRUCKBAY Pit opening 1.10 m Pit length per meter
VZ 920034	TRUCKBAY Pit opening 1.22 m Pit length per meter
VZ 920035	TRUCKBAY Divider over 29 m length (up to max. 42 meters)
VZ 920036	TRUCKBAY Pit lane Length 2 m Storage space in working pit
VZ 920037	TRUCKBAY Swallow's nest Length 1 m for assy units Storage space in working pit
VZ 920038	TRUCKBAY Bus hatch with traversable grating in double wall design
VZ 920093	TRUCKBAY Transverse aisle between two installation pits with staircase
VM 999086	TRUCKBAY Extra material costs Cross aisle between pits
VZ 920094	TRUCKBAY Lateral pit access
VM 999087	TRUCKBAY Extra material costs Lateral pit access
VZ 920039	TRUCKBAY Pit stairs
VZ 920095	TRUCKBAY Access ladder
VZ 920040	TRUCKBAY Park position under pit stairs
VZ 920041	TRUCKBAY ROLL COVER SOLO, for basic prefabr. pit MODEL: ROLLCOVER 15
VZ 920042	TRUCKBAY ROLL COVER TANDEM, for basic prefabr. pit MODEL: ROLLCOVER 16
VZ 920043	TRUCKBAY ROLL COVER for SOLO and TANDEM Pit length per meter
VM 999084	TRUCKBAY ROLL COVER Mounting material MTZ Pit length per meter
VZ 920044	TRUCKBAY ROLL COVER Enlarged pit opening 1.10 m Base frame -ON REQUEST-
VZ 920045	TRUCKBAY ROLL COVER Enlarged pit opening 1.10 m, Pit length per meter -ON REQUEST-
VZ 920046	TRUCKBAY ROLL COVER Enlarged pit opening 1.22 m Base frame -ON REQUEST-
VZ 920047	TRUCKBAY ROLL COVER Enlarged pit opening 1.22 m, Pit length per meter -ON REQUEST-
VZ 920048	TRUCKBAY ROLL COVER Reinforced steel cover, up to 13 t axle load -ON REQUEST-
VM 996251	Installation costs ROLL-COVER Pit length per meter -NET PRICE-
VZ 920049	Pipe socket for media routing Access to TRUCKBAY DN 110
VZ 920050	Pipe socket for media routing Access to TRUCKBAY DN 150
VZ 920051	Pipe socket for media routing Access to TRUCKBAY DN 200
VZ 920052	Pipe socket for media routing Access to TRUCKBAY DN 315
VZ 920053	Holding rail 590 mm
VZ 920054	Holding rails 200 mm
VZ 920055	TRUCKBAY Basic electrical equipment
VZ 920056	TRUCKBAY Electrical equipment Pit length per meter
VZ 920108	TRUCKBAY 10 mm² sub-distribution board 36 units -NET EXTRA CHARGE-
VZ 920057	Double wall socket 230 V / 16 A, per piece
VZ 920058	Wall socket 400 V / 16 A, per piece
VZ 920059	Main switch incl. connection to pit sub-distribution for separate control
VZ 920060	Protective cover for electrical sub-distribution
VZ 920097	Control cabinet version: Netherlands -NET EXTRA CHARGE-
VZ 920098	Control cabinet version: Belgium -NET EXTRA CHARGE-
VZ 920099	Control cabinet version: France/Luxembourg -NET EXTRA CHARGE-
VZ 920100	Control cabinet version: Scandinavian -NET EXTRA CHARGE-
VZ 920101	Control cabinet version: Swiss -NET EXTRA CHARGE-
VZ 920061	LED tube lamp Light output 3800 lm per item
VZ 920062	Time relay for pre-run of pit extraction, 400 V
VZ 920063	Submersible pump with float switch for pump sump
VZ 920064	Compressed air supply 5 m Safety couplings, 2 pcs with maintenance unit
VZ 920065	Compressed air supply 10 m Safety couplings, 3 pcs with maintenance unit
VZ 920066	Compressed air supply 15 m Safety couplings, 4 pcs with maintenance unit
VZ 920067	Compressed air supply 20 m Safety couplings, 5 pcs with maintenance unit
VZ 920068	Compressed air supply 25 m Safety couplings, 6 pcs with maintenance unit
VZ 920102	Permanent oil disposal channel TECALEMIT basicchannel -NET PRICE-
VZ 920103	Permanent oil disposal channel TECALEMIT, per meter -NET PRICE-
VZ 920104	Additional trolley for continuous waste oil disposal TECALEMIT system
VZ 920105	Pump w. intermediate oil tank 13 l, for TECALEMIT permanent waste oil disposal system
VZ 920071	Waste oil collector w. swivel hopper, approx. 60 l capacity
VZ 920106	Intermediate oil tank TECALEMIT, 90 l -NET PRICE-
VZ 920073	Waste oil tank 450 l Installation under pit stairs
VZ 920074	TRUCKBAY frame for axle play tester LMS 20.0
VZ 920075	TRUCKBAY frame, extra charge for flush-mounted axle play tester LMS 20.0
VZ 920107	TRUCKBAY frame for axle play tester LMS 20.0 TL
VZ 920096	TRUCKBAY cover, extra charge for flush-mounted axle play tester LMS 20.0
VZ 920076	TRUCKBAY frame for roller brake tester MBT 7000
VZ 920077	TRUCKBAY frame for brake tester with roller set lift MBT 7000
VZ 920109	TRUCKBAY frame for brake tester with roller set lift MBT 7000 TL
VZ 920078	TRUCKBAY frame brake tester weighing device MBT 4000
VZ 920079	Cover between roller sets for TRUCKBAY
VZ 920110	TRUCKBAY Transport Separation Point MBT 7000 -NET PRICE-
VZ 920111	TRUCKBAY Piping for DIN EN 17003 Mounting preparation for GSL
VZ 920112	TRUCKBAY Mounting preparation for GSL -NET PRICE-

VZ 920080	TRUCKBAY preparation for MAHA floor anchor
VZ 920081	TRUCKBAY preparation for MAHA weight simulator
VZ 920082	Guide rail per meter for floor-guided pit jacks
VZ 920040	TRUCKBAY Park position under pit stairs
VM 996234	Installation of provided pit jack, floor-guided
VM 996235	Installation of provided pit jack, suspended
VZ 920083	Coating of top pit edge with SafeStep 50, per meter
VZ 920084	Extra charge for painting prefabr. pit in special colour RAL colour on request
VZ 920085	Preparation of first approval drawing
VZ 920086	Subsequent change of approval drawing per drawing
VZ 920087	Mounting for heavy duty rollers to transport the TRUCKBAY through workshop gate
VZ 920088	Basic wooden cover Building protection cover
VZ 920089	Wooden cover Building protection cover Pit length per meter

SUPPLEMENTARY CHARGES

VV 997597	Packing, securing and delivery of provided accessories
VM 996236	TRUCKBAY loading costs in case of collection
VT 998154	TRUCKBAY transport to installation site -ON REQUEST
VM 996237	TRUCKBAY installation costs on site -ON REQUEST